Dragon Forge Artistic Ironworks.

D. McNeil & Sons.

Archway 2,

Little Burton West,

Burton-on-Trent,

Staffordshire.

DE14 1PP.

Tel: 07891402220.

Email : davidmcneil1210@gmail.com

29th December 2015.

Quotation : Tutbury War Memorials Preservation Committee.

St.Mary's Priory Church, Tutbury.

Wreath Holders.(x2) Sizes as specified in original scaled drawing.

Materials as follows: Posts - 50x50x8 mild steel box with 40mm sphere top.

Vertical bars - 16mm solid mild steel round bar with finials

to match finials on church entrance gates.

Horizontal flat - 30x10 mild steel.

Cross holders – 15x5 mild steel.

Leaf/flower stems - 8mm mild steel solid round bar.

Flower petals, leaves – 2mm mild steel.

Completed structures to be galvanised then primed using a high build anti corrosive zinc phosphate primer and finished with satin black specialised metal paint. Panel segments will be made to bolt together using galvanised nylock nuts.

Fixed to ground by bedding in concrete to depth of 400mm.

Each complete panel is made up of 2 wreath holder panels and 1 central decorative poppy panel.

Price per complete panel £1500.00.

2 complete panels to be supplied.

Price includes all labour and material/paint costings.

Total cost £3000.00.

Deposit required of 1/3 of total cost.

All cheques made payable to : D.McNeil.